



FORMULAS for estimating Eco-Grip Job Materials

Estimated Square & Linear Feet: exactly as measured or surveyed – NO WASTE

Sheet Count: measured square feet x 1.05 / 40, rounded up = # sheets for floor

Sheet Count (BASE): ½ measured linear feet x 1.05 / 40, rounded up = # sheets for base

Base Cap Molding: estimated linear feet included 13 self-tapping screws per 8' length – screws ordered separately. Sold by the carton – 400' per

E-6100 Sealant: estimated linear feet 25 = tubes (add 5% for retrofit projects) – Sold by the case- 12 tubes per.

2-Part Epoxy: total square feet (floor & base) estimated / 80 = # gallons. Approximately 1 gallon per 2 sheets of material. **Please divide total square feet by 60 when estimating retrofit/remodel projects over existing flooring, i.e. tile or poured floors.**

Conventional Weld: 13 linear feet per sheet installed

SpeedFlex 490 mL Cartridge: 60 linear feet of liquid welded seam.

SpeedFlex Mixing Tips: 1-2 cartridge of SpeedFlex liquid weld. Each case of SpeedFlex will included 12 mixing tips. Always order a few extras.

SpeedFlex Seam Tape: 180 ft per roll. Tape both sides of the seam.

Stainless Steel Accessories (collar or flange): 1 per floor drain, floor sink, clean out, trench drain or grease trap

Stainless Threshold: Measured linear feet screws & anchors: (lf x 2)

Anchors/#10 screws: 2 each per every lineal feet of threshold; plus 8 each per each drain collar/flange; plus 40 each per trench drain flange

Standard Trowel Size: 3/32" notch

Cleaning Kit: include one on every purchase order. (Hot water hose, gallon of degreaser, deck brush, foam gun & squeegee included).

Continual use of Eco-Grips degreaser will double the warranty to 10 years